

# ACME CONSTRUCTION CO

1565 Cummins Dr., Modesto, CA 95358

Phone: 209.523.2674

Fax: 209.523.0213

Date: 9/20/2021

TO:	COMPANY:	FAX:	PHONE:
Estimating	North State Electric		530-519.1147

**Project:** Accubid Office Building

**Location:** 1010 Marauder Street  
Chico, CA 95926

**Trade:** Electrical

## ADDENDUM #4

For equipment shutdown on activation of Fire Alarm system, a 1/2" conduit with two (2) #14 conductors will be run from the Fire Alarm Control Panel to the starters for AHU-1, AHU-2 and EF-1 (3 separate runs for the FACP). These pairs of #14 to be connected to the normally closed sets of dry contacts in the FACP and will control the operation of the equipment shutdowns with selector switches in the "Auto" position.